



## Trailer Mounted Test Unit

The ABU-100 (Automatic Batch Unit, 100 gallon) is used to demonstrate the onsite treatability of customer's wastewater. The units require 30 amps (with the



optional blower) at 120 volts to operate (#10 3 wire extension cord). The setup requires a contact from the customers sump pump to close when the sump pumps is turned On, this starts the fill cycle. The unit operates automatically, filling, treating, and dewatering, then repeating as long as there is water to be treated in the sump.

The unit is available for rental.

40308 Greenwood Way  
Oakhurst, Ca. 93644

Phone (559) 683-8284  
Fax (559) 683-8913

[www.wecleanwater.com](http://www.wecleanwater.com)  
[sales@wecleanwater.com](mailto:sales@wecleanwater.com)